

440 W NYACK ROAD WEST NYACK, NY

PROJECT INFORMATION

SCHOOL AND SPECIAL DISTRICTS

FIRE: CLARKSTOWN
SCHOOL: CLARKSTOWN CENTRAL
WATER:
SEWER: ROCKLAND COUNTY SEWER DISTRICT #1
LIBRARY:

SHEET LIST

C-001	TITLE PAGE
C-020	SOIL EROSION AND SEDIMENT CONTROL
C-100	SITE PLAN
C-110	SUBSURFACE AND DRAINAGE PLAN
C-200	PROFILES - IN PROGRESS
C-300	CULTEC DETAILS
C-310	TYPICAL DETAILS
C-400	EROSION CONTROL


OWNER: THE SALVATION ARMY
440 WEST NYACK ROAD WEST NYACK, NY 10994

ZONING INFORMATION


440 WEST NYACK ROAD WEST NYACK, NY 10994
TOWN: CLARKSTOWN SECTION: 58.19 BLOCK: 1 LOT: 10
ZONE: CO - COMMERCIAL OFFICE LOT AREA: 24.37 ACRES

PROJECT NARRATIVE

PROPOSED NEW ONE-STORY COMMERCIAL BUILDING WITH PARKING LOT, DRIVEWAYS, STORMWATER MANAGEMENT, AND NEW UTILITY CONNECTIONS



A VICINITY MAP
SCALE: 1" = 300'-0"



B EXISTING SURVEY
SCALE: 1" = 200'-0"

LEGEND:

	PROPOSED STORM COMPONENT
	PROPOSED STORM SYSTEM
	IMPERMEABLE ROOF
	BUILDING FOOTPRINT
	GRASS YARD
	EXISTING SITE STRUCTURE
	STORM CATCH BASIN
	ADJACENT BUILDING
	STREET TREE
	SEWER CLEANOUT
	PROPERTY LINE
	STORM LINE
	MAJOR TOPO CONTOUR
	MINOR TOPO CONTOUR
	PROPOSED TOPO CONTOUR
	10' OFFSET FROM COMPONENT
	AREA OF WORK / DISTURBANCE
	SILT FENCE
	EXISTING TREE TO REMAIN (WITH DRIP LINE)
	EXISTING TREE TO BE REMOVED (NONE)
	NEW PAVEMENT
	PAVEMENT / STRUCT. T.B.R.
	TREE PROTECTION FENCE
	DRIVEWAY STATION
	TREE LINE
	EXISTING SPOT ELEVATION
	PROPOSED SPOT ELEVATION

CONSTRUCTION NOTES:

- EXISTING UTILITIES AND UNDERGROUND STRUCTURES SHOWN ON THE PLAN ARE BASED UPON THE BEST AVAILABLE PUBLIC RECORDS, PRIVATE RECORDS AS SUPPLIED BY THE OWNER, OR DATA OBTAINED VERBALLY FROM OWNERS OR OFFICIALS FAMILIAR WITH THE PROJECT SITE. NEITHER THE OWNER NOR THE ENGINEER GUARANTEE ACCURACY OR COMPLETENESS OF THIS INFORMATION AND ASSUME NO RESPONSIBILITY FOR IMPROPER LOCATIONS ON THE CONSTRUCTION PLANS. OTHER UNDERGROUND FACILITIES NOT SHOWN ON THE DRAWINGS MAY BE ENCOUNTERED DURING THE COURSE OF THE WORK. ALL INVERT ELEVATIONS SHOWN ON THE DRAWINGS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
- IF CHANGED CONDITIONS ARE ENCOUNTERED, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF EITHER (1) PREEXISTING SUBSURFACE CONDITIONS DIFFERING FROM THOSE INDICATED IN THE PLANS, OR (2) PREEXISTING UNKNOWN SUBSURFACE CONDITIONS OF AN UNUSUAL NATURE, DIFFERING MATERIALLY FROM THOSE ORIGINALLY ENCOUNTERED AND GENERALLY RECOGNIZED AS INHERENT IN THE CHARACTER OF THE WORK PROVIDED FOR IN THE CONTRACT. THE CONTRACTOR AND/OR OWNER SHALL MAKE NO CLAIMS TO THE ENGINEER FOR RECOMPENSATION FOR EXTRA WORK RESULTING FROM CHANGED CONDITIONS UNLESS THE ENGINEER HAS APPROVED THE WORK IN WRITING.
- CONTRACTOR SHALL PROVIDE ALL NECESSARY PERMITS AND APPROVED CITY ORDINANCES AND SHALL POST SUCH DOCUMENTS AT VISIBLE LOCATIONS AND MAINTAIN UPDATED DOCUMENTATION ACCORDINGLY.
- CONTRACTOR SHALL CALL THE UTILITIES UNDERGROUND LOCATION CENTER FOR FIELD LOCATIONS OF ALL UTILITIES AND SHALL NOT BEGIN EXCAVATION UNTIL ALL KNOWN UNDERGROUND FACILITIES IN THE VICINITY OF THE PROPOSED WORK HAVE BEEN LOCATED AND MARKED. IF THE UTILITY IS NOT A SUBSCRIBER OF THE UTILITIES UNDERGROUND LOCATION CENTER, THEN THE CONTRACTOR SHALL GIVE NOTICE TO THAT UTILITY.
- THE CONTRACTOR IS RESPONSIBLE FOR REVIEW OF ALL INFORMATION PROVIDED BY UTILITY PURVEYORS, AND CITY OR STATE RECORDS RELATED TO THE EXISTING UNDERGROUND UTILITIES. THE CONTRACTOR IS RESPONSIBLE FOR AVOIDING DAMAGE TO THESE FACILITIES AND SHALL RESTORE ALL UTILITIES AT CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL NOTIFY ALL UTILITY SERVICES FOR TEMPORARY SHUT OFF AS REQUIRED. CONTRACTOR SHALL MAINTAIN AND PROTECT SERVICES AGAINST DAMAGE DURING DEMOLITION OPERATIONS.
- NO PUBLIC WAYS OR WALKS MAY BE OBSTRUCTED WITHOUT THE WRITTEN PERMISSION OF GOVERNING AUTHORITIES AND OF THE OWNER. WHERE ROUTES ARE PERMITTED TO BE CLOSED, PROVIDE ALTERNATE ROUTES AND SIGNAGE IF REQUIRED.
- WET DEBRIS WITH WATER AS NECESSARY TO LIMIT DUST TO LOWEST PRACTICAL LEVEL. DO NOT WET TO THE EXTENT OF FLOODING, CONTAMINATED RUNOFF, OR ICING.
- ANY PORTIONS OF PAVEMENT TO BE REMOVED MUST BE SEPARATED BY MAKING A NEAT VERTICAL SAW CUT ALONG THE BOUNDARIES OF THE AREA TO BE REMOVED. MAKE CUTS AT CLOSEST PAVING JOINT.
- PROVISIONS SHALL BE MADE TO ALLEVIATE THE SPREAD OF DEBRIS, DIRT, AND DUST TO THE ADJACENT PROPERTIES. THE PROPERTY SHALL BE KEPT AS CLEAN AS POSSIBLE AT ALL TIMES. MAINTAIN HAULING ROUTES CLEAN AND FREE OF ANY DEBRIS RESULTING FROM DEMOLITION WORK ON THIS PROJECT. ANY HAZARDOUS MATERIAL REMOVAL, SUCH AS ASBESTOS REMOVAL, SHALL BE PERFORMED PRIOR TO ANY DEMOLITION ACTIVITY. THE HAZARDOUS MATERIAL REMOVAL SHALL BE PERFORMED BY A LICENSED ABATEMENT COMPANY.
- THE REFUSE RESULTING FROM ANY CLEARING AND GRUBBING AND ALL DEBRIS AND MATERIALS FROM THE STRUCTURE(S) TO BE DEMOLISHED SHALL BE DISPOSED OF BY THE CONTRACTOR IN A MANNER CONSISTENT WITH ALL GOVERNMENT REGULATIONS. IN NO CASE SHALL REFUSE MATERIAL BE LEFT ON THE PROJECT SITE, PUSHED ONTO ADJUTING PRIVATE PROPERTIES, OR BE BURIED IN EMBANKMENTS OR TRENCHES ON THE PROJECT SITE. DEBRIS SHALL NOT BE DEPOSITED IN ANY STREAM, LAKE, WETLAND, BODY OF WATER, OR IN ANY STREET OR ALLEY, OR UPON ANY PRIVATE PROPERTY EXCEPT BY WRITTEN CONSENT OF THE PRIVATE PROPERTY OWNER. NO RECLAIMED LUMBER OR MATERIALS SHALL BE RE-USED EXCEPT AS SPECIFICALLY APPROVED BY THE ARCHITECT OR OWNER.

SANITARY SEWER LINE REQUIREMENTS

- CLEANOUTS SHALL BE PROVIDED ON SEWER LINES WHEREVER A GRADE CHANGE OR ALIGNMENT CHANGE IS MADE (SEE CLEANOUT DETAIL FOR MORE INFO)
- SEWER LINES SHALL BE SEPARATED FROM POTABLE WATER LINES BY A MINIMUM OF 10' HORIZONTAL
- SEWER LINES CROSSING POTABLE WATER LINES JOINTS MUST BE MINIMUM OF 18" BELOW WATER LINES. WATER LINES MUST BE MINIMUM 10" FROM POINT OF CROSSING. SEWER LINES ARE TO BE MINIMUM 10" FROM POINT OF CROSSING. SEWER LINES ARE TO BE CONSTRUCTED TO STANDARDS EQUIVALENT TO WATER MAIN SPECIFICATIONS AND SHALL BE PRESSURE TESTED PRIOR TO BACKFILLING
- GRAVITY LINES SHALL BE A MINIMUM OF 4"
- LINES MUST BE OF CAST IRON PIPE FOR A MINIMUM DISTANCE OF 2' BEYOND FOUNDATION WALL
- GRAVITY LINES TO BE PITCHED MINIMUM 1/4" VERTICAL PER 1' HORIZONTAL, UNLESS NOTED OTHERWISE
- TRENCHES ARE TO BE FIRMLY TAMPED BY HAND ABOUT THE PIPE

ENGINEERED FILL
BANKRUN SAND & GRAVEL SHALL BE OBTAINED FROM AN APPROVED COMMERCIAL MANUFACTURER AND SHALL HAVE A PERCOLATION RATE OF LESS THAN 5 MIN / INCH & GREATER THAN 1 MIN / INCH. THE SUPPLIER SHALL PROVIDE A WRITTEN ANALYSIS AND CERTIFY TO THE ROCKLAND COUNTY HEALTH DEPARTMENT AND TO THE DESIGN ENGINEER THAT THE MATERIAL DELIVERED TO THIS SITE HAS BEEN MANUFACTURED BY THEM AND MEETS THE DESIGN ENGINEER'S SPECIFICATION FOR BANKRUN SAND & GRAVEL. THE CONTRACTOR SHALL EXCAVATE THE ABSORPTION BED AREA TO BEDROCK AND HAVE THE EXCAVATION INSPECTED AND APPROVED BY THE ROCKLAND COUNTY HEALTH DEPARTMENT PRIOR TO PLACEMENT OF THE BANKRUN SAND & GRAVEL.

SEPTIC CONSTRUCTION NOTES

- HEAVY CONSTRUCTION EQUIPMENT SHALL BE KEPT OUTSIDE THE PROPOSED BOTTOM AREA OF THE BED
- THE REQUIRED BED BOTTOM AREA IS EXCAVATED AS LEVEL AS PRACTICAL. THE BOTTOM AND SIDES OF THE EXCAVATION ARE HAND RAKED TO REDUCE SOIL SMEARING
- AFTER EXCAVATIONS A SIX-INCH LAYER OF AGGREGATE BELOW PIPE AND COVERED WITH AGGREGATE TO A LEVEL TWO INCHES ABOVE THE TOP OF THE PIPE
- THE ENTIRE BED AREA IS TO BE COVERED WITH A PERMEABLE GEOTEXTILE

SITE/CIVIL CONSTRUCTION SEQUENCING:

- INSTALL SILT FENCE, EROSION CONTROL, AND CONSTRUCTION FENCE
- INSTALL SITE STRUCTURES AND ROUGH REGRADING
- REMOVE ALL DEBRIS
- INSTALL ALL ADDITIONAL EROSION CONTROL AND STABILIZATION OF DEMO. AREAS
- INSTALL SUBSURFACE UTILITIES, SEPTIC SYSTEM & ROUGH SITEWORK (MINOR REGRADING)
- PROVIDE TEMP. SEEDING / SODDING & EROSION CONTROL MEASURES
- REMOVE EXISTING PARKING / STAGING AREA
- PERFORM FINISH GRADING
- REMOVE TEMP. EROSION CONTROL MEASURES. INSTALL NEW PERMANENT LANDSCAPING. SITE STABILIZATION (80% UNIFORM DENSITY OF VEGETATION) MUST BE ACHIEVED PRIOR TO REMOVING TEMPORARY EROSION CONTROL MEASURES.

NARRATIVE

NEW SEPTIC SYSTEM TO BE INSTALLED / REPAIRED. NEW 1000 AND 1250 GAL SEPTIC TANKS TO BE INSTALLED. NEW PUMP TANK, DISTRIBUTION BOX, AND ABSORPTION BED TO BE INSTALLED

REVISIONS:

IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW, ARTICLE 141, FOR ANY PERSON, UNLESS HE OR SHE IS ACTING UNDER THE DIRECTION OF A PROFESSIONAL ENGINEER, TO SEAL OR SIGN DRAWINGS OR ANY OTHER DOCUMENTS OF THIS PROJECT.

THE ENGINEER'S SIGNATURE AND SEAL ARE REQUIRED FOR ALL DRAWINGS. THE ENGINEER'S SIGNATURE AND SEAL ARE REQUIRED FOR ALL DRAWINGS. THE ENGINEER'S SIGNATURE AND SEAL ARE REQUIRED FOR ALL DRAWINGS.

PROJECT:
440 WEST NYACK ROAD
WEST NYACK, NY

PROPOSED SITE PLAN

SEAL & SIGNATURE:

JOREL J. VACCARO, PE
NY PE 093362

DATE: 10/03/2024
PROJECT #: 23069
DRAWN/CHECKED: P.J.M./J.V.
SCALE: 1" = 30'-0"
PAGE: 01 OF 08



A PROPOSED SESC PLAN
 SCALE: 1" = 30'-0"




REVISIONS:

IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW, ARTICLE 142, FOR ANY PERSON, UNLESS HE OR SHE IS ACTING UNDER THE DIRECTION OF A PROFESSIONAL ENGINEER, TO SEAL OR SIGN ANY DRAWING OR SPECIFICATION.

PROJECT:
**440 WEST NYACK ROAD
 WEST NYACK, NY**

**SOIL EROSION &
 SEDIMENT CTRL PLAN**


SEAL & SIGNATURE:




JOREL J. VACCARO, PE
 NY PE 083362

BY THE REST OF THE DRAWING PROFESSIONAL'S KNOWLEDGE, THE PLANS AND SPECIFICATIONS CONFORM WITH ALL APPLICABLE REGULATORY CODES.

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: 1" = 30'-0"
 PAGE: 02 OF 08



A PROPOSED SITE PLAN
 SCALE: 1" = 30'-0"



B PROPOSED COVERAGES
 SCALE: 1" = 100'-0"




REVISIONS:

IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW, ARTICLE 141, FOR ANY PERSON, UNLESS HE OR SHE IS ACTING UNDER THE DIRECTION OF A PROFESSIONAL ENGINEER, TO SEAL THIS DRAWING IN ANY WAY.
 THE ENTIRE CONTENTS OF THIS DOCUMENT INCLUDING ALL LETTERS, PLANS, NOTES, SPECIFICATIONS, SCHEDULES AND ADDENDUMS, AND ALL COMMERCIAL OFFERS, CONTRACTS, AGREEMENTS, AND OTHER DOCUMENTS, HEREBY REFERRED TO AS "THE DOCUMENT" AND THEIR CONTENTS, MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN CONSENT OF KRYPTON ENGINEERING, P.C. ORIGINALS MUST BE KEPT.

PROJECT:
 440 WEST NYACK ROAD
 WEST NYACK, NY


PROPOSED SITE PLAN

SEAL & SIGNATURE:



JOREL J. VACCARO, Inc.
 NY PE 083362
 DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: 1" = 30'-0"
 PAGE: 03 OF 08

C-100.00



A PROPOSED SITE PLAN
 SCALE: 1" = 30'-0"

REVISIONS:

NO.	DATE	DESCRIPTION

PROJECT:
 440 WEST NYACK ROAD
 WEST NYACK, NY

PROPOSED STORM & SUBSURFACE


SEAL & SIGNATURE:

JOREL J. VACCARO, PE
 NY PE 093362


DATE:	10/03/2024
PROJECT #:	23069
DRAWN/CHECKED:	PJM/JLV
SCALE:	1" = 30'-0"
PAGE:	04 OF 08

C-110.00


connector-road-alignment PROFILE




east-driveway-alignment PROFILE




west-driveway-alignment PROFILE



water-alignment PROFILE



sanitary-sewer-alignment PROFILE



REVISIONS:

IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW, ARTICLE 141, FOR ANY PERSON UNLESS HE OR SHE IS ACTING UNDER THE DIRECTION OF A PROFESSIONAL ENGINEER, TO REPRODUCE OR COPY THIS DRAWING IN ANY WAY.

THE ENTIRE CONTENTS OF THIS DOCUMENT, INCLUDING ALL SPECIFICATIONS, PLANS, SCHEDULES, DRAWINGS, CALCULATIONS AND NOTIFICATIONS, ARE THE PROPERTY OF KRYPTON ENGINEERING, LLC. THE DOCUMENTS AND THEIR CONTENTS MAY NOT BE COPIED, REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN CONSENT OF KRYPTON ENGINEERING, LLC. ORIGINAL SHEET SIZE: 11x17

PROJECT:
**440 WEST NYACK ROAD
 WEST NYACK, NY**


PROFILES
 CIVIL DETAILS

SEAL & SIGNATURE:


JOREL I. VACCARO, PE
 NY PE 093362

DATE: 05/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: PJM/JLV
 SCALE: NOTED
 PAGE: 02 OF 04


C-200.00




1 CATCH BASIN
SCALE: NTS




2 TRENCH DRAIN
SCALE: NTS




3 UTILITY DRAIN
SCALE: NTS




4 INFILTRATION BASIN
SCALE: NTS




5 PAVEMENT REPAIR
SCALE: NTS




6 STORM WATER RETENTION SYSTEM
SCALE: NTS




7 WATER-SEWER CROSSING
SCALE: NTS




8 CURB TYPICAL DETAIL
SCALE: NTS




9 EX'G SEWER ABANDONMENT
SCALE: NTS




10 RIP RAP APRON TYPICAL DETAIL
SCALE: NTS



11 WATER SERVICE LINE LATERAL CONNECTION
SCALE: NTS




12 CLEANOUT TYPICAL DETAIL
SCALE: NTS



14 DRIVEWAY CROSS SECTION
SCALE: NTS



13 WHEEL STOP TYPICAL DETAIL
SCALE: NTS



16 CURB CUT PLAN AND SECTIONS
SCALE: NTS

REVISIONS:

PROJECT:
**440 WEST NYACK ROAD
 WEST NYACK, NY**



TYPICAL SITE
 CIVIL DETAILS

SEAL & SIGNATURE:

JOREL J. VACCARO, PE
 NY PE 083362



DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: NOTED
 PAGE: 07 OF 08

C-310.00




- CONCRETE WASHOUT**
- NOTES:
- NO WASHING OUT OF CONCRETE TRUCKS OR WASHING OF SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE INTO STORM DRAINS, OPEN DITCHES, STREETS OR STREAMS IS ALLOWED.
 - EXCESS CONCRETE IS NOT ALLOWED TO BE DUMPED ON-SITE, EXCEPT IN DESIGNATED TEMPORARY CONCRETE WASHOUT FIT AREAS.
 - ON-SITE TEMPORARY CONCRETE WASHOUT AREAS WILL BE LOCATED AT LEAST 50 FEET FROM STORM DRAINS, OPEN DITCHES, OR WATER BODIES AS DETERMINED IN THE FIELD.
 - TEMPORARY CONCRETE WASHOUT FACILITIES WILL BE CONSTRUCTED AND MAINTAINED IN SUFFICIENT QUANTITY AND SIZE TO CONTAIN ALL LIQUID AND CONCRETE WASH GENERATED BY WASHOUT OPERATIONS.
 - WASHOUT FACILITIES WILL BE CLEANED OUT OR REPLACED ONCE THE WASHOUT IS 75% FULL.
 - PLASTIC LINING MATERIAL WILL BE A MINIMUM OF 10 MIL POLYETHYLENE SHEETING AND WILL BE FREE OF HOLES, TEARS, OR ANY OTHER DEFECTS.
 - WHEN WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR WORK, THE HARDENED CONCRETE WILL BE REMOVED AND DISPOSED OF OFFSITE. MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES WILL BE REMOVED FROM THE SITE AND DISPOSED OF PROPERLY.

DETAIL - CONCRETE WASHOUT




- DETAIL - SOIL STOCKPILE**
- NOTES:
- TOPSOIL REMOVED DURING SITE PREPARATION SHALL BE STOCKPILED ON-SITE FOR FUTURE USE IN SITE RECLAMATION AND REVEGETATION.
 - SOIL STOCKPILE SHALL BE ENCLOSED WITH SILT FENCING WITH PASSAGEWAY PROVIDED FOR EQUIPMENT ACCESS.
 - PROVIDE TEMPORARY GRASS OR MULCH COVER IF STOCKPILE IS TO REMAIN UNDISTURBED FOR THIRTY DAYS OR MORE. TEMPORARY COVER SHALL CONSIST OF ONE OF THE FOLLOWING MEASURES:
 - GRASS SEED: 1/2 LB. RYE GRASS / 1000 SF.
 - MULCH: 100 LBS OF STRAW OR HAY / 1000 SF.

DETAIL - SOIL STOCKPILE




- DETAIL - SILT FENCE**
- NOTES:
- POST SPACING TO BE 10' MAX. O.C.
 - WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES.
 - WOVEN WIRE FENCE TO BE 14 GA. MIN., 6" MAX. SPACING.
 - FILTER CLOTH TO BE FILTER X, MIRAFI 100X OR APPROVED EQUAL.
 - FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE, WITH WIRE TIES SPACED EVERY 24" AT TOP AND MID SECTION.
 - WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED OR TIED TO A POST (PROVIDE POST AT SPICE).
 - MAINTENANCE SHALL BE PERFORMED AS NEEDED, AND MATERIAL REMOVED WHEN BULGES DEVELOP IN THE SILT FENCE.
 - BALES SHALL BE PLACED AT THE TOE OF SLOPE OR ON THE CONTOUR AND IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.
 - EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF (4) INCHES, AND PLACED SO THE BINDINGS ARE HORIZONTAL.
 - BALES SHALL BE SECURELY ANCHORED IN PLACE BY EITHER TWO STAKES OR REBARS DRIVEN THROUGH THE BALE. THE FIRST STAKE IN EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE AT AN ANGLE TO FORCE THE BALES TOGETHER. STAKES SHALL BE DRIVEN 1 1/2 TO 2" INTO THE GROUND AND FLUSH WITH THE BALE.
 - INSPECTION SHALL BE FREQUENT AND REPAIR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
 - BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULNESS SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

DETAIL - SILT FENCE



- DROP INLET PROTECTION DETAIL**
- CONSTRUCTION SPECIFICATIONS:
- CLEAR THE AREA OF ALL DEBRIS THAT WILL HINDER EXCAVATION.
 - GRADE APPROACH TO THE INLET UNIFORMLY AROUND THE BASIN.
 - WEEP HOLES SHALL BE PROTECTED BY GRAVEL.
 - UPON STABILIZATION OF CONSTRUCTION DRAINAGE AREA, SEAL WEEP HOLES, FILL BASIN WITH STABLE SOIL TO FINAL GRADE, COMPACT SOIL PROPERLY AND STABILIZE WITH PERMANENT SEEDING.


DROP INLET PROTECTION DETAIL



- STABILIZED CONSTRUCTION ENTRANCE**
- CONSTRUCTION SPECIFICATIONS:
- STONE SIZE - USE 2" STONE OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
 - LENGTH - AS REQUIRED, BUT NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY).
 - THICKNESS - NOT LESS THAN (6) INCHES.
 - WIDTH - TEN (10) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
 - FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. FILTER WILL NOT BE REQUIRED ON A SINGLE FAMILY RESIDENCE LOT.
 - SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCE SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPE WILL BE PERMITTED.
 - MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANING OF ANY MEASURE USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAYS MUST BE REMOVED IMMEDIATELY.
 - WASHING - WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAYS. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
 - PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

STABILIZED CONSTRUCTION ENTRANCE

- EROSION CONTROL:**
- ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE INSTALLED IN ACCORDANCE WITH THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN STATE STANDARDS AND WILL BE INSTALLED IN PERMANENT SEQUENCE AND MAINTAINED UNTIL PERMANENT STABILIZATION IS ESTABLISHED.
 - ANY DISTURBED AREA THAT WILL BE LEFT EXPOSED FOR MORE THAN THIRTY (30) DAYS AND NOT SUBJECTED TO CONSTRUCTION TRAFFIC SHALL IMMEDIATELY RECEIVE TEMPORARY SEEDING AND MULCHING. IF THE SEASON PROHIBITS TEMPORARY SEEDING, THE DISTURBED AREA WILL BE MULCHED WITH SALT HAY OR EQUIVALENT AND BOUND IN ACCORDANCE WITH THE NY STANDARDS (I.E. PEG AND TWINE, MULCH NETTING, OR LIQUID MULCH BINDER).
 - IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR TROUGH GRADING, ALL CRITICAL AREAS SUBJECTED TO EROSION WILL RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH OR SUITABLE EQUIVALENT, AT A RATE OF 2 TONS PER ACRE, ACCORDING TO NY STANDARDS.
 - STABILIZATION SPECIFICATIONS:
 - TEMPORARY SEEDING AND MULCHING:
 - LIME - 90 LBS / 1,000 SF GROUND LIMESTONE; FERTILIZER - 11 LBS / 1,000 SF, 10-20-10 OR EQUIVALENT WORKED INTO THE SOIL A MINIMUM OF 4".
 - SEED - PERENNIAL RYE GRASS 40 LBS./ACRE (1 LB / 1,000 SF) OR OTHER APPROVED SEEDS, PLANT BETWEEN MARCH 1 AND MAY 15 OR BETWEEN AUGUST 15 AND OCTOBER 1.
 - MULCH - SALT HAY OR SMALL GRAIN STRAW AT A RATE OF 70 TO 90 LBS./1,000 SF TO BE APPLIED ACCORDING TO THE NY STANDARDS. MULCH SHALL BE SECURED BY APPROVED METHODS (I.E. PEG AND TWINE, MULCH NETTING, OR LIQUID MULCH BINDER).
 - PERMANENT SEEDING AND MULCHING:
 - TOPSOIL - UNIFORM APPLICATION TO A DEPTH OF 5" (UNSETTLED).
 - LIME - 90 LBS / 1,000 SF GROUND LIMESTONE; FERTILIZER - 11 LBS / 1,000 SF, 10-20-10 OR EQUIVALENT WORKED INTO THE SOIL A MINIMUM OF 4".
 - SEED TURF TYPE TALL FESCUE (BLENDED OF 3 CULTIVARS) 150 LBS./ACRE (3.5 LBS./1,000 SF) OR OTHER APPROVED SEED, PLANT BETWEEN MARCH 1 AND OCTOBER 15.
 - MULCH - SALT HAY OR SMALL GRAIN STRAW AT A RATE OF 70 TO 90 LBS./1,000 SF TO BE APPLIED ACCORDING TO THE NY STANDARDS. MULCH SHALL BE SECURED BY APPROVED METHODS (I.E. PEG AND TWINE, MULCH NETTING, OR LIQUID BINDER).
 - THE SITE SHALL AT ALL TIMES BE GRADED AND MAINTAINED SUCH THAT ALL STORM WATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.
 - SOIL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSPECTED AND MAINTAINED ON A REGULAR BASIS, INCLUDING AFTER EVERY STORM EVENT.
 - STOCKPILES ARE NOT TO BE LOCATED WITHIN 50' OF A FLOOD PLAIN SLOPE, ROADWAY OR DRAINAGE FACILITY. THE BASE OF ALL STOCKPILES SHALL BE CONTAINED BY A STRAW BALE SEDIMENT BARRIER AND/OR SILT FENCE.
 - A CRUSHED STONE, VEHICLE WHEEL-CLEANING BLANKET WILL BE INSTALLED WHEREVER A CONSTRUCTION ACCESS ROAD INTERSECTS ANY PAVED ROADWAY. SAID BLANKET WILL BE COMPOSED OF 1" - 2" CRUSHED STONE, 6" THICK, WILL BE AT LEAST 30 X 100' AND SHOULD BE UNDERLAIN BY A SUITABLE SYNTHETIC SEDIMENT FILTER FABRIC AND MAINTAINED.
 - MAXIMUM SIDE SLOPES OF ALL EXPOSED SURFACES SHALL NOT EXCEED 3:1 UNLESS OTHERWISE APPROVED BY THE ENGINEER.
 - DRIVEWAYS MUST BE STABILIZED WITH 1" - 2" CRUSHED STONE OR SUBBASE PRIOR TO INDIVIDUAL LOT CONSTRUCTION.
 - ALL SOIL WASHED, DROPPED, SPILLED OR TRACKED OUTSIDE THE LIMIT OF DISTURBANCE OR INTO PUBLIC RIGHT-OF-WAYS, WILL BE REMOVED IMMEDIATELY. PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES.
 - CATCH BASIN INLETS WILL BE PROTECTED WITH AN INLET FILTER DESIGNED IN ACCORDANCE WITH NY STANDARDS.
 - STORM DRAINAGE OUTLETS WILL BE STABILIZED, AS REQUIRED, BEFORE THE DISCHARGE POINTS BECOME OPERATIONAL.
 - DEWATERING OPERATIONS MUST DISCHARGE DIRECTLY INTO A SEDIMENT CONTROL BAG OR OTHER APPROVED FILTER IN ACCORDANCE WITH NY STANDARDS.
 - DUST SHALL BE CONTROLLED VIA THE APPLICATION OF WATER, CALCIUM CHLORIDE OR OTHER APPROVED METHOD IN ACCORDANCE WITH NY STANDARDS.
 - TREES TO REMAIN AFTER CONSTRUCTION ARE TO BE PROTECTED WITH A SUITABLE FENCE INSTALLED AT THE DRIP LINE OR BEYOND IN ACCORDANCE WITH NY STANDARDS.
 - THE PROJECT OWNER SHALL BE RESPONSIBLE FOR ANY EROSION OR SEDIMENTATION THAT MAY OCCUR BELOW STORM WATER OUTFALLS OR OFF-SITE AS A RESULT OF CONSTRUCTION OF THE PROJECT.
 - ANY REVISION TO THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN MUST BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO IMPLEMENTATION IN THE FIELD.
 - A COPY OF THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE THROUGHOUT CONSTRUCTION.
 - SILT FENCINGS SHALL BE ADJUSTED IN FIELD AND NOT ENCRoACH ONTO EXISTING TREES TO REMAIN AND SHALL ENCOMPASS LIMITS OF DISTURBANCE INCLUDING SEEPAGE PIT LOCATIONS.
 - THE TREE PROTECTION AND PRESERVATION WILL BE IMPLEMENTED IN ORDER TO PROTECT AND PRESERVE BOTH INDIVIDUAL SPECIMEN TREES AND BUFFER AREA WITH MANY TREES. STEPS THAT WILL BE TAKEN TO RESERVE AND PROTECT EXISTING TREES TO REMAIN ARE AS FOLLOWS:
 - NO CONSTRUCTION EQUIPMENT SHALL BE PARKED UNDER THE TREE CANOPY.
 - THERE WILL BE NO EXCAVATION OR STOCKPIILING OF EARTH UNDERNEATH THE TREES.
 - TREES DESIGNATED TO BE PRESERVED SHALL BE MARKED CONSPICUOUSLY ON ALL SIDES AT A 5 TO 10 FOOT HEIGHT.
 THE TREE PROTECTION ZONE FOR TREES DESIGNATED TO BE PRESERVED WILL BE ESTABLISHED BY ONE OF THE FOLLOWING METHODS:
 - ONE (1) FOOT RADIUS FROM TRUCK PER INCH DBH.
 - DRIP LINE OF THE TREE CANOPY.
 THE METHOD CHOSEN SHOULD BE BASED ON PROVIDING THE MAXIMUM PROTECTION ZONE POSSIBLE. A BARRIER OF SNOW FENCE OR EQUAL IS TO BE PLACED AND MAINTAINED ONE YARD BEYOND THE ESTABLISHED TREE PROTECTION ZONE. IF IT IS AGREED THAT THE TREE PROTECTION ZONE OF A SELECTED TREE MUST BE VIOLATED, ONE OF THE FOLLOWING METHODS MUST BE EMPLOYED TO MITIGATE THE IMPACT.
 - LIGHT TO HEAVY IMPACTS - MINIMUM OF EIGHT INCHES OF WOOD CHIPS INSTALLED IN THE AREA TO BE PROTECTED. CHIPS SHALL BE REMOVED UPON COMPLETION OF WORK.
 - LIGHT IMPACT ONLY - INSTALLATION OF 3/4 INCH OF PLYWOOD OR BOARDS, OR EQUAL OVER THE AREA TO BE PROTECTED. THE BUILDER OR ITS AGENT MAY NOT CHANGE GRADE WITHIN THE TREE PROTECTION ZONE OF A PRESERVED TREE UNLESS SUCH GRADE CHANGE HAS RECEIVED FINAL APPROVAL FROM THE PLANNING BOARD. IF THE GRADE LEVEL IS TO BE CHANGED MORE THAN (6) INCHES, TREES DESIGNATED TO BE PRESERVED SHALL BE WELLED AND/OR PRESERVED IN A RAISED BED, WITH THE TREE WELL A RADIUS OF THREE (3) FEET LARGER THAN THE TREE CANOPY.
 - PRIOR TO THE COMMENCEMENT OF ANY SITE WORK, INCLUDING THE REMOVAL OF TREES, THE CONTRACTOR SHALL INSTALL THE SOIL EROSION AND SEDIMENTATION CONTROL AS REQUIRED BY THE DRAWINGS. PRIOR TO THE AUTHORIZATION TO PROCEED WITH ANY PHASE OF THE SITE WORK, THE ENGINEER SHALL BE NOTIFIED IN ADVANCE TO INSPECT THE INSTALLATION OF ALL REQUIRED SOIL EROSION AND SEDIMENTATION CONTROL MEASURES. THE CONTRACTOR SHALL CONTACT THE ENGINEER AT LEAST 48 HOURS IN ADVANCE FOR AN INSPECTION.
 - ALL LANDSCAPING SHOWN ON THE SITE PLANS SHALL BE MAINTAINED IN A VIGOROUS GROWING CONDITION THROUGHOUT THE DURATION OF THE USE OF THIS SITE. ANY PLANTS NOT SO MAINTAINED SHALL BE REPLACED WITH NEW PLANTS AT THE BEGINNING OF THE NEXT IMMEDIATELY FOLLOWING GROWING SEASON.
 - IF THE CONTRACTOR, DURING THE COURSE OF CONSTRUCTION, ENCOUNTERS SUCH CONDITIONS AS FLOOD AREA, UNDERGROUND WATER, SOFT OR SILTY AREAS, IMPROPER DRAINAGE, OR ANY OTHER UNUSUAL CIRCUMSTANCES OR CONDITIONS THAT WERE NOT FORESEEN IN THE ORIGINAL PLANNING, SUCH CONDITIONS SHALL BE REPORTED IMMEDIATELY TO THE ENGINEER OF RECORD. THE CONTRACTOR MAY SUBMIT THEIR RECOMMENDATIONS AS TO THE SPECIAL TREATMENT TO BE GIVEN SUCH AREAS TO SECURE ADEQUATE, PERMANENT AND SATISFACTORY CONSTRUCTION.
 - THE CONTRACTOR'S TRAILER, IF ANY IS PROPOSED, SHALL BE LOCATED AS APPROVED BY THE MUNICIPALITY.
 - PERMANENT VEGETATION COVER OF DISTURBED AREAS SHALL BE ESTABLISHED ON THE SITE WITHIN THIRTY (30) DAYS OF THE COMPLETION OF CONSTRUCTION.



- TREE PROTECTION DETAIL**
- NOT TO SCALE
- THE PROJECT DEVELOPER SHALL TAKE REASONABLE PRECAUTION TO SAVE SPECIMEN QUALITY TREES IN AREAS NOTED ON THE PLANS FOR CLEARING. WHEN POSSIBLE, THE DEVELOPER SHALL PROTECT INDIVIDUAL SPECIMEN TREES THROUGH THE INSTALLATION OF SAFETY FENCING AROUND THE DRIP LINE PERIMETER OF THE TREE.
 - SAFETY FENCING SHALL BE INSTALLED AT THE ONSET OF SITE CONSTRUCTION TO PREVENT VEHICLE TRAFFIC FROM COMPACTING THE SOILS IN THE VICINITY OF THE TREE ROOT STRUCTURE.

TREE PROTECTION DETAIL

REVISIONS:

PROJECT:
 440 WEST NYACK ROAD
 WEST NYACK, NY

EROSION CONTROL TYPICAL DETAILS

SEAL & SIGNATURE:

JOREL J. VACCARO, PE
 NY PE 083362

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

DATE: 10/03/2024
 PROJECT #: 23069
 DRAWN/CHECKED: P.J.M./J.V.
 SCALE: AS NOTED
 PAGE: 08 OF 08

C-400.00