


1 Third Floor - Key Plan
1/16" = 1'-0"




2 Roof Key Plan
1/16" = 1'-0"

General Notes

A. REFER TO BM051 FOR GENERAL NOTES.

Keyed Notes

① TEMPORARILY REMOVE CONDENSING UNIT AND STORE FOR REUSE. EVACUATE AND LABEL (WITH RCU SYSTEM) ALL REFRIGERANT PRIOR TO REMOVAL. DISCONNECT AND REMOVE REFRIGERANT TUBING AS REQUIRED UNTIL COMPLETION OF ROOFING WORK. REINSTALL CONDENSING UNIT ON EXISTING SUPPORTS SYSTEM. RECONNECT REFRIGERANT TUBING AND CHARGE UNIT WITH CAPTURED REFRIGERANT. PROVIDE ADDITIONAL REFRIGERANT AS REQUIRED TO REACH REFRIGERANT DESIGN SYSTEM PRESSURE. INSULATE REFRIGERANT TUBING. COORDINATE WITH ROOFING WORK.



Key Plan
N.T.S.

S.E.D. Control No. 62-18-01-06-0-002-015

Rev. No.	Date	Description



complex world | CLEAR SOLUTIONS

Tetra Tech Engineers, Architects & Landscape Architects, P.C.

BID SET



Walkkill Central School District
Walkkill, New York

Reconstruction to:
John G. Borden Middle School

Third Floor and Roof Key Plans

Drawn By: JPF/pgm	Date: 06/30/2023	Drawing Number:
Project No.: 17597-22002	BM052	