



1 First Floor Demolition Plan - Area B
1/8" = 1'-0"

Keyed Notes

- 1 REMOVE LUMNAIRES, LIGHTING CONTROLS COIL AND TAG CIRCUITRY FOR REUSE.
- 2 REMOVE THE CEILING DEVICES, PRESERVE CIRCUITRY AND STORE FOR REINSTALLATION. COORDINATE ALL WORK WITH GENERAL CONTRACTOR.
- 3 DISCONNECT AND REMOVE ELECTRICAL CIRCUITRY BACK TO SOURCE. LABEL BREAKER AS SPARE AND UPDATE PANELBOARD SCHEDULE.
- 4 REMOVE WALL MOUNTED DEVICES TO ACCOMMODATE CEILING REPLACEMENT. PRESERVE / STORE DEVICES AND CIRCUITRY AS NECESSARY FOR REINSTALLATION. COORDINATE ALL WORK WITH GENERAL CONTRACTOR.

General Notes

A. REFER TO DRAWING BE100 FOR GENERAL DEMOLITION NOTES
B. SEE SHEET G-001 FOR SYMBOLS LEGEND AND ABBREVIATIONS
C. REFER TO BE600 PANEL BOARD SCHEDULES FOR ADDITIONAL INFORMATION

Key Plan
N.T.S.

N

S.E.D. Control No. 62-18-01-06-0-002-015

Rev. No.	Date	Description

WALLKILL
CENTRAL SCHOOL DISTRICT

complex world
CLEAR SOLUTIONS

BID SET

TETRA TECH
ARCHITECTS & ENGINEERS

Walkkill Central School District
Walkkill, New York

Reconstruction to:
John G. Borden Middle School

First Floor Demolition Plan - Area B

Drawn By: GLK/CR/ded	Date: 06/30/2023	Drawing Number: BE101
Project No.: 17597-22002		