PLUMBING FIXTURE SCHEDULE												
1.OR APPROVED EQUA	R APPROVED EQUAL											
TVDF		BASIS OF DESIGN	MODEL	CONNECTION SIZE					DEMARKS			
TAG	ТҮРЕ	MANUFACTURER	MODEL	CW	HW	W	IW	V	REMARKS			
DPCO	DECK PLATE CLEANOUT	ZURN	Z1400			3"						
FD-1	FLOOR DRAIN	ZURN	Z415B			2"		2"	PROVIDE TRAP SEAL			
LAV-1	LAV WALL HUNG	KOHLER	K-2007	1/2"	1/2"	1 1/2"		1 1/2"	WITH FAUCET EAF-100 WITH PLUG, SEE ARCHITECTURAL FOR FINAL MOUNTING HEIGHTS			
LAV-2	LAV WALL HUNG (ADA)	KOHLER	K-2007	1/2"	1/2"	1 1/2"		1 1/2"	WITH FAUCET EAF-100 WITH PLUG, SEE ARCHITECTURAL FOR FINAL MOUNTING HEIGHTS			
UR-1	URINAL	KOHLER	K-4991-ET	3/4"		2"		2"	WITH FLUSH VALVE SLOAN ECOS 186 HW			
WC-1	WATER CLOSET WALL HUNG	ZURN	Z5615	1"		4"		2"	WITH FLUSH VALVE SLOAN ECOS 111 (HW), SEE ARCHITECTURAL FOR FINAL MOUNTING HEIGHTS			
WC-2	WATER CLOSET WALL HUNG (ADA)	ZURN	Z5615	1"		4"		2"	WITH FLUSH VALVE SLOAN ECOS 111 (HW), SEE ARCHITECTURAL FOR FINAL MOUNTING HEIGHTS			
WC-4	WATER CLOSET FLOOR MOUNTED	ZURN	Z5655-BWL1	1"		4"		2"	WITH FLUSH VALVE SLOAN ECOS 111 (HW)			

WEEP HOLES

FINISHED FLOOR

─ FLOOR DRAIN

— NO-HUB COUPLING

CLAMPING COLLAR

SECONDARY STRAINER

FLOOR DRAIN WITH ABOVE FLOOR PIPING DETAIL

12" = 1'-0"

WATERPROOF MEMBRANE

4 4 4 4 4


INTO MORTAR BED


						500 600				
WATER HAMMER ARRESTOR										
	MODEL NUMBER									
SHOKTROL Z1700	100	200	300	400	500	600				
FIXTURE RATING	1-11	12-32	33-60	61-113	114-154	155-330				
TAG	WHA-A	WHA-B	WHA-C	WHA-D	WHA-E	WHA-F				

6/19/2024 10:15:41 AM

CIRCULATOR PUMP SCHEDULE											
1. CIRCULATING HOT WATER PUMP, STAINLESS STEEL, NSF-61 RATED.											
TAG	LOCATION	ТҮРЕ	CAPACITY	HEAD (FT. W.C.)	ELECTRICAL DATA VOLTS PH HP			BASIS OF DESIGN MFG. AND MODEL	REMARKS		
RP-1	BOILER ROOM	CARTRIDGE CIRCULATOR	2 GPM	2	115	1	1/40	TACO 003B			

14





ABBREVIATIONS LEGEND PLUMBING LEGEND \_\_\_ \_ \_ COLD WATER PIPING (CW) ABOVE FINISHED FLOOR ABOVE FINISHED GRADE AVERAGE BELOW FINISHED FLOOR \_\_\_\_\_ HOT WATER RECIRC PIPING (HWR) BRAKE HORSEPOWER BOTTOM OF PIPE SANITARY ABOVE GRADE BTUH
CAP
CO
CONT.
CW
DCW BRITISH THERMAL UNITS/HOUR CAPACITY SANITARY BELOW GRADE CLEAN OUT \_ \_ \_ \_ \_ SAN\_\_ \_ \_ CONTINUATION DOMESTIC COLD WATER — — — — — — WASTE PIPING DOMESTIC COLD WATER DIAMETER DOWN W———— NATURAL GAS PIPING DPCO DWG ES DECK PLATE CLEAN OUT EMERGENCY EYE WASH/SHOWER STATION \_\_\_\_\_ PIPE RISER UP SYMBOL EXPANSION TANK ENTERING WATER TEMPERATURE BRANCH PIPE CONNECTOR OFF BOTTOM OF PIPING MAIN DEGREES FAHRENHEIT FRESH AIR INTAKE FD FLA FLR FT. OR ' FLOOR DRAIN MID-PIPE DOWN FULL LOAD AMPS FLOOR FEET GAS PIPE DOWN WITH VALVE IN VERTICAL GALLON GPH GPM GALLONS PER HOUR UNION **GALLONS PER MINUTE** HOSE BIBB CLEAN OUT HORSEPOWER HOUR PIPING/EQUIPMENT REMOVALS HW HWR HZ DOMESTIC HOT WATER HOT WATER RECIRCULATION HERTZ CHECK VALVE IN OR " INT INCHES INTERNAL INDIRECT WASTE KITCHEN SINK KSK SHUTOFF BALL VALVE KILOWATT PRESSURE REDUCING VALVE LENGTH LAVATORY LEAVING AIR TEMPERATURE PLUG VALVE <del>−</del> PUMP LINEAR FOOT LEAVING WATER TEMPERATURE THOUSAND BTUH FLOOR DRAIN MOTORIZED DAMPER CLEANOUT DECKPLATE MAXIMUM NOT APPLICABLE GATE VALVE NORMALLY CLOSED MANUFACTURER BUTTERFLY VALVE MIDDLE SCHOOL ELECTRONIC MIXING VALVE BALANCE VALVE NORMALLY OPEN NON OVER LOADING PLUMBING CONTRACTOR PRESSURE DROP POINT OF REMOVAL PARTS PER MILLION OR POINT OF CONNECTION POUNDS PER SQUARE INCH POUNDS PER SQUARE INCH GAUGE **ROOF DRAIN** ROOF LEADER ROOF OVERFLOW DRAIN RECIRCULATION PUMP REVOLUTIONS PER MINUTE REDUCED PRESSURE ZONE GAS FIRED ROOFTOP UNIT S OR SAN SANITARY SQUARE FOOT SHOWER

SHORT RADIUS SERVICE SINK/JANITOR'S SINK STORM PIPING TEMPERATURE

THERMOSTATIC MIXING VALVE

WATER HAMMER ARRESTOR

CONCRETE REPAIR BY
 CONSTRUCTION WORK
 CONTRACTOR

EXISTING CONCRETE FLOOR

- COMPACTED SUBBASE,

COURSE TYPE 2, MIN 6" DEPTH

ALL SIDES OF PIPE

- CUSHION MATERIAL MIN. 6" ON

 WASTE PIPING, REFER TO PLUMBING PLANS FOR PIPE SIZES

TYPICAL URINAL VENT VERTICAL

VENT THRU ROOF WASTE WATER CLOSET WALL CLEAN-OUT WATER HEATER ksqdesigr

NEW YORK OKLAHOMA

ARCHITECT

KSQ Design
215 W 40th Street 15th Floor
New York, NY 10018
646.435.0660 office
www.ksq.design

Nanuet Union Free School District
101 Church Street
Nanuet, NY 10954
845.627.9880
www.nanuetsd.org

Structural Engineer

Clapper Structural Engineering
160 Partition Street

Saugerties, NY 12477
845.943.9601
www.clapperstructural.com

MEP Engineer

Sage Engineering Associates, LLP
9 Columbia Circle
Albany NY 12203
518.453.6091
www.sagellp.com
NYS CERTIFICATE AUTHORZIATION NUMBER 8018644

Environmental Engineer

Quest Environmental Solutions
1376 Route 9
Wappingers Falls, NY 12590
845.298.6251
www.qualityenv.com

www.jacobs.com

Construction Manager

Jacobs
One Penn Plaza
24th Floor, Suite 2400
New York, NY 10119
646.908.6550





NUFSD BOND PROJECT PHASE 5 -HIGHVIEW

■ SED#50-01-08-03-0-002-020 (HIGHVIEW ES)

□ SED#50-01-08-03-7-007-002 (Maintenance)

□ SED#50-01-08-03-7-012-004 (OEC)

□ SED#50-01-08-03-0-001-026 (MILLER ES)

□ SED#50-01-08-03-0-004-022 (BARR MS)

Highview Elementary School
24 Highview Ave
Nanuet, NY 10954


OEC Building
135 Convent Rd

Nanuet, NY 10954

<u>Maintenance Building</u>
103 Church St.
Nanuet, NY 10954

Miller Elementary School 50 Blauvelt Rd Unit1 Nanuet, NY 10954

A MacArthur Barr Middle School 143 Church St Nanuet, NY 10954



No. Description

ISSUED: BID SET

ISSUED: BID SET

DATE: 06/21/2024

SCALE: NTS

SHEET NAME:

LEGENDS, SCHEDULES,
AND DETAILS

SHEET NUMBER:
HE-P001

PROJECT NUMBER: 00000.00 COPYRIGHT © 2023 KSQ ARCHITECTS, PC